



BOB KELLER

Design: LeTourneau Technologies Tarzan Class
 Built: Vicksburg, Mississippi
 Year Built / Last Upgrade: 2005 / 2022



Premium Jackup

General Description

Classification..... ABS, A1 Self-elevating Drilling Unit.
 Flag Marshall Islands.
 Overall Dimensions (Hull) 215.33 ft. long x 196 ft. wide x 22 ft. deep.
 Legs 3 x 445.45 ft. long, triangle.
 Longitudinal Leg Centers.....121.67 ft.
 Transverse Leg Centers.....140.50 ft.
 Drafts15.94 ft. load line draft.
 Accommodation110 persons.
 Displacement..... 25,806.22 kips operating.
 Variable Deck Load 7,633.08 kips operating / 3,177.26 kips transit.
 Transit Speed average 3 knots (min. 300 kips combined bollard pull).
 Operating Water Depth 300 ft.
 Maximum Drilling Depth 35,000 ft.

Drilling Equipment

Derrick Woolslayer base, 36 ft. X 36 ft, 170 ft.
 Hook load Capacity 2,000,000 lbs. on 16 Lines static hook load capacity.
 Top Drive National Oilwell PS-2 750A, 7500 psi rated 1,500 hp AC motor, output torque 79,000 ft lbs continuous at 250 rpm.
 Cantilever / Drill Floor 50 ft aft of Transom / 60 ft with Extension Beam.
 Travelling Block LEWCO, LBLK-1000,1000 Ton.
 Crown Block Woolslayer / SCB-55 Rated Capacity 2,000,000 lbs.
 Drawworks Lewco 4500, Driven by (2) 1,500 hp AC Motors with 1-3/4 - inch Drill Line.
 Auxiliary Brake NOV Baylor 15050 W.
 Rotary Table Lewco D495, 49-1/2 Inch, Capacity 1,250 tons, Driven by (1) OEM 400 hp AC Motor.
 Cementing Eqpt. HEC, working pressure 15,0000 psi with 2 triplex pumps.
 Torque Wrench NOV ST-100 Torque Wrench, size 3-1/2" to 9-3/4".

Mud System

Mud Pumps (3) Letourneau Ellis William W-3000, Triplex, 2 Motors for each pump (2 ea.) Letourneau AC Motors, power rating 1500 hp.
 HP Mud System Rated for 7,500 psi.
 Mud Pits 2181 bbls + 2099 bbls Reserve Mud Tank.
 Desanders & Desilters (1) Derrick FLC 500 w/3 - 10" poly cones 1,200 gpm.
 (1) Derrick FLC 500 w/20 - 4" poly cones 1,200 gpm.
 Degasser (1) Derrick VAC-FLO-1200 at 1200 gpm.
 Shale Shakers (4) Derrick Flowline Cleaners 750 gpm each.

Storage Capacities

Fuel Oil..... 5,505 bbls.
 Liquid Mud.....4,280 bbls (6pits + 2 slug pits + 1 comb tank).
 Base Oil 726 bbls.
 Drill Water 7,190 bbls (incl. combo tanks).
 Potable Water 1,582 bbls.
 Bulk Material (Barite/Bentonite + Cement) 11,882 cu.ft.
 Sack Storage 775 sq. ft.
 Pipe Storage (Main) 2,400 sq. ft. x 7ft. high.
 Pipe Storage (Cantilever) 2,352 sq. ft. x 7ft. high.

BOP & Well Control

BOP (1) 18-3/4" 10K Annular.
 (1) 18-3/4" 15K (2ea Double Cameron type "TL")
 (1) 26-3/4" 3K & 30" 1K Annular.
 BOP Handling (2) EMCE, Pneumatic Chain Hoist 125 Ton each hoist.
 Diverter GE Vetco Gray, Model KFDJ 500 psi.
 Control Unit Cameron, 3k psi BOP Control Unit (80) 15 gal. bottles with reservoir tank capacity 950 gal.
 Choke Manifold 4-1/16" 15K Upstream to 4-1/16" 10K Downstream

Power & Machinery

Main Power (5) Caterpillar 3516BHD V16, diesel engines rated 2,150 hp
 (5) Kato 6P6-3000 Generator rated at 1,540kw.
 Emergency Power (1) Caterpillar 3516BHD V16 diesel engines rated 2,150 hp
 (1) Kato C060-6422 Generator rated at 1,540kw.

Cranes

Deck Cranes (3) Letourneau PCM 220VS Pedestal Crane, SWL 50 tons.

Special Features & Other Information

Helideck Sikorsky S-61N. D 22.2 M, SWL 12.8 tons.
 Jacking 6 pinions per chord, 3 x chords per leg, 1000 kips per pinion for holding capacity and 440 kips per pinion for Jacking capacity.



